

MANNINGTON MILLS INC. TEST SUMMARY

SCOPE OF WORK

ANSI B101.3 DCOF (WET) SLIP RESISTANCE TESTING OF TEST SAMPLE K - 294630
(BIOSPEC MD - ELDERBERRY)

PROJECT NUMBER

N5242.01-106-31 R0

TEST DATES

03/23/22 - 03/24/22

ISSUE DATE

04/29/22

RECORD RETENTION END DATE

03/24/26

PAGES


3

DOCUMENT CONTROL NUMBER

ATI 00810 (09/05/17)

RT-R-AMER-Test-2778

© 2017 INTERTEK



TEST SUMMARY FOR MANNINGTON MILLS INC.

Project No.: N5242.01-106-31 R0

Date: 04/29/22

SUMMARY ISSUED TO

MANNINGTON MILLS INC

75 Mannington Mills Road
Salem, New Jersey 08079

SECTION 1

SCOPE

Architectural Testing, Inc. (an Intertek company) dba Intertek Building & Construction (B&C) was contracted by Mannington Mills Inc to witness testing of Sample K - 294630 (Biospec MD - Elderberry). Witnessed testing was in general accordance with ANSI B101.3. Results obtained are tested values and were secured by using the designated test methods. Testing was conducted at the Mannington Mills facility in Salem, New Jersey.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

Unless differently required, Intertek reports apply the "Simple Acceptance" rule, also called "Shared Risk approach," of ILAC-G8:09/2019, Guidelines on Decision Rules and Statements of Conformity.

For INTERTEK B&C:

COMPLETED BY:	Cooper F. Kennedy	REVIEWED BY:	Scott D. Scallorn
TITLE:	Technician III Natural Stone & Cementitious Materials	TITLE:	Program Manager Natural Stone & Cementitious Materials
SIGNATURE:		SIGNATURE:	
DATE:	04/29/22	DATE:	04/29/22

CFK:sds/alts

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

TEST SUMMARY FOR MANNINGTON MILLS INC.

Project No.: N5242.01-106-31 R0

Date: 04/29/22

SECTION 2

TEST METHODS

The specimens were evaluated in general accordance with the following:

ANSI B101.3-2012, *Test Method for Measuring Wet DCOF Of Common Hard-Surface Floor Materials*

Deviation: Instead of testing Wet DCOF with a surfactant solution of 0.1% Sodium Lauryl Sulfate in distilled water as the method calls for, testing was performed using deionized water on all specimen types.

SECTION 3

TEST RESULTS

ANSI B101.3 Wet DCOF - Test Sample K (Biospec MD - Elderberry)

TEST ID	WET DCOF MEASUREMENT (Distilled Water)						TEST LOCATION AVERAGE
	DIRECTION	NO.					
		1	2	3	4	5	
K - Wet - 1	180° - 0°	0.56	0.55	0.58	0.57	0.56	0.57
	270° - 90°	0.56	0.53	0.55	0.55	0.56	
	0° - 180°	0.57	0.58	0.59	0.59	0.59	
	90° - 270°	0.58	0.57	0.58	0.57	0.57	
K - Wet - 2	180° - 0°	0.57	0.58	0.57	0.57	0.56	0.57
	270° - 90°	0.55	0.55	0.57	0.55	0.55	
	0° - 180°	0.56	0.57	0.55	0.58	0.57	
	90° - 270°	0.57	0.57	0.58	0.57	0.57	
K - Wet - 3	180° - 0°	0.59	0.58	0.59	0.59	0.58	0.58
	270° - 90°	0.56	0.56	0.56	0.57	0.56	
	0° - 180°	0.57	0.60	0.60	0.60	0.60	
	90° - 270°	0.56	0.58	0.58	0.58	0.58	
Wet Test Series Mean							0.57

SECTION 4

CONCLUSION

This is a summary of a larger test report, for full program details, procedures and reference photographs please see Intertek B&C Report No. **N5242.01-106-47**. This summary alone is not a complete report.